NOTICE TO BIDDERS

SEALED PROPOSALS will be accepted by the Coolbaugh Township Board of Supervisors until 2:00 P.M. on Thursday May 14, 2026, at the Coolbaugh Township Municipal Center, 5520 Municipal Drive, Tobyhanna, PA 18466, at which time they will be publicly opened and read for the following work:

Base Bid and Additional Bid Items

1,246 Tons of Superpave 9.5 mm, Scratch/Leveling Course, placed 60 LB/SY
3,741 Tons of Superpave 9.5 mm, Wearing Course, placed 180 LB/SY
972 Tons of 2A Crushed Aggregate Subbase, placed as Shoulder Back-up
16,204 Lineal Feet of Double Yellow Center Lines with Glass Beads
17,284 Lineal Feet of Single White Edge Lines with Glass Beads

All materials and workmanship must meet the requirements and standards of PennDOT Publication 408 – *Specifications*, and bidders must be PennDOT pre-qualified for Work Class "F" Bituminous Paving.

Proposals must be on forms provided by the Township. Proposal forms, specifications and bid information may be obtained on the Township website. Interested parties can view and download the documents by visiting www.coolbaughtwp.org and navigating to the Public Notice page or by contacting the Coolbaugh Township Secretary by phone at 570-894-8490 x3, or by email at emasker@coolbaughtwp.org. For further information or to schedule a road inspection, call 570-894-8334.

All bids must be accompanied by a certified check or bid bond in the amount of ten (10%) percent of the bid made payable to Coolbaugh Township.

The successful bidder will be required to provide Performance and Payment Bonds, each in the amount of 100% of the contract price within 20 days of the award of the contract.

The bids will be presented to the Coolbaugh Township Board of Supervisors at the scheduled regular meeting on Monday May 18, 2026, at approximately 6:00 P.M., or as soon thereafter as the agenda allows, at which time they will be considered, and the contract may be awarded.

The Coolbaugh Township Board of Supervisors reserves the right to accept or reject any and/or all proposals or portions thereof, and to delete projects and or portions of the project depending on budgetary constraints and also to waive any technicalities deemed to be in the best interest of the Township.

Pennsylvania Prevailing Wages apply to this contract.

All work must be completed by September 30, 2026; liquidated damages will apply at the rate of $975 per day for each day beyond this date that the work remains incomplete.

Coolbaugh Township Board of Supervisors
5520 Municipal Drive
Tobyhanna, PA 18466

END OF ADVERTISEMENT

Publish on Monday, April 13, 2026, and Monday, April 20, 2026
Send bill and proof of advertising to Coolbaugh Township Board of Supervisors.

PROPOSAL & CONTRACT (WHEN EXECUTED)

(THIS PROPOSAL INCLUDES INSTRUCTIONS TO BIDDERS)

A. DEPOSIT OF PROPOSALS.

All Enveloped containing Bid proposals shall be clearly marked **"2026 Road Paving Bid Proposal for Letting of May 14, 2026"**

Sealed Proposals will be received on or before
2:00 p.m., on Thursday, May 14, 2026
Time and Date

Bids will be opened and read at approximately
2:00 p.m., on Thursday, May 14, 2026
Time and Date

Tentative Award Date and Time
6:00 p.m., on Monday, May 18, 2026
Time and Date

Coolbaugh Township **(570) 894-8490**
Municipality Name and Type Telephone

Erin Masker
Secretary

5520 Municipal Drive
Address

Tobyhanna, PA 18466
Proposals must be mailed or otherwise delivered to the above address.

1. The contractor proposes to furnish and deliver all materials (including Form CS-4171, Certificate of Compliance, TR-465 Daily Bituminous Mixture Certification or other form pre-approved by PennDOT) and to do and perform all work on the following project as more specifically set forth in the Schedule of Prices (Attachment), in accordance with drawings and specifications on file at the **Coolbaugh Township Municipal Center** at the above address.
As well as the supplements and special requirements contained herein and/or attached hereto and current PennDOT Publication 408 – *Specifications*, **bidders need to be prequalified by PennDOT (Sec. 102.01).**

2. If designated as the successful bidder, the contractor will begin work on the date specified in the notice to proceed. Or as otherwise provided in the special requirements, and will complete all work on or before **September 30, 2026**. If all work is not completed on time, liquidated damages will be assessed at the rate of **$975.00** per additional calendar day.

3. Accompanying this proposal is a certified check or bid Bond in the amount of **10%** made payable to the municipality as a proposal guarantee which, it is understood, will be forfeited in case the contractor fails to comply with the requirement of the proposal.

B. PROPOSAL OF: _____

Name of Contractor

_____

Address

CONTRACTOR'S CERTIFICATION

It is hereby certified as follows:

1. The only person(s) interested in this proposal as principal(s) is (are): _____
_____
_____

2. None of the above persons are employees of the municipality.

3. This proposal is made without collusion with any other person, firm, or corporation.

4. All plans and specifications referred to above and the site of the work have been examined by the contractor. The contractor understands that the quantities indicated herein are approximate and are subject to change as may be required; and that all work is payable on the basis of the unit prices listed on the Schedule of Prices (Attachment #1).

5. The contractor will comply with all requirements of the laws and implementing regulations of the Commonwealth of Pennsylvania and the United States relating to human relations, equal opportunity, and non-discrimination in employment, and will pay to workmen employed in the performance of the contract the wages to which they may be entitled.

6. The contractor will provide the municipality with a 100% performance bond, conditioned upon the faithful performance of the contractor in accordance with the plans, specifications and conditions thereof, and a 100% payment bond conditioned on the prompt payment of all material furnished and labor supplied or performed in the prosecution of the work, in accordance with the Public Work's Contractors' Bond Law of 1967; and an affidavit accepting the provisions of the Workmen's Compensation Act of 1915, as amended.

7. "The parties agree that the relationship between the Contractor and the Municipality is one of independent contractor and not the employer/employee and that the individual employees of the Contractor who will be performing the work pursuant to this contract are not employees of the Municipality. Contractor hereby certifies, represents and warrants to the Municipality that all persons performing any aspect of the work pursuant to this Contract who are required to have commercial driver's license are subject to a program for drug and alcohol testing in accordance with the Omnibus Transportation Employee Testing Act of 1991 and the federal regulations adopted pursuant thereto."

_____
Contractor

WITNESSED OR ATTESTED BY:

BY: _____
Title (Seal)

_____
Title

SEAL

TO BE EXECUTED ONLY IN THE EVENT THE ABOVE PROPOSAL IS ACCEPTED

Item Numbers Included in Contract: _____

ACCEPTED ON: _____
Date

_____
Municipality

ATTESTED BY:

_____ BY: _____
Title Title

SEAL

_____
Title

_____
Title

ATTACHMENT #1

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

THIS PORTION TO BE COMPLETED BY THE MUNICIPALITY

LOCATION OF WORK:

Various Township Roads within Coolbaugh Township; see Attachment #1-B

DESCRIPTION OF WORK:
As indicated below and in Attachments #1-A and #1-B. The Contractor is to place the type and depth of material listed in the Schedule of Prices. All depths to be compacted in place and work shall include tack coat as per PennDOT Publication 408, *Specifications*, milling of pavement notches at intersecting roads and driveways and sealing of joints and utilities, and temporary centerline markings. Hand or machine placed roll bituminous curb may be required. These items are to be incidental to the paving.

ESCALATOR CLAUSE: (If adopted by the Municipality)
This contract contains sufficient quantities of asphalt cement for the PennDOT bituminous price adjustment to apply. PennDOT Publication 408, Section 110.04 will apply to quantities of bituminous materials greater than 100 tons of asphalt cement including asphalt cement residue contained in emulsions or cutbacks. **(See Attachment 1-A for more information).**

SCHEDULE OF PRICES

BASE BID ROADS

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
			Kings Way, T-715		
1	129	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
2	387	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
3	106	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
4	1,761	LF	4" Double Yellow Center Line with Glass Beads		
5	3,522	LF	4" Single White Edge Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Kings Way SUBTOTAL**	

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

SCHEDULE OF PRICES
BASE BID ROADS, Continued

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
			Salamanca Lane, T-655		
6	184	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
7	553	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
8	166	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
9	2,767	LF	4" Double Yellow Center Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Salamanca Lane SUBTOTAL**	
			Echo Lake Road, T-591 (1)		
10	315	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
11	946	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 180 LB/SY		
12	218	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
13	3,640	LF	4" Double Yellow Center Line with Glass Beads		
14	7,280	LF	4" Single White Edge Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Echo Lake Road (1) SUBTOTAL**	

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

SCHEDULE OF PRICES
BASE BID ROADS, Continued

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total

Echo Lake Road, T-591 (2)

15	133	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
16	398	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 180 LB/SY		
17	92	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
18	1,531	LF	4" Double Yellow Center Line with Glass Beads		
19	3,062	LF	4" Single White Edge Line with Glass Beads		

*DESCRIPTION
Must include ADT on Wearing surfaces.
USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.

Echo Lake Road (2) SUBTOTAL

Echo Lake Road, T-591 (3)

20	84	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
21	252	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 180 LB/SY		
22	58	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
23	970	LF	4" Double Yellow Center Line with Glass Beads		
24	1,940	LF	4" Single White Edge Line with Glass Beads		

*DESCRIPTION
Must include ADT on Wearing surfaces.
USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.

Echo Lake Road (3) SUBTOTAL

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

SCHEDULE OF PRICES
BASE BID ROADS, Continued

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
Heath Lane, T-645					
25	50	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
26	151	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
27	41	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
28	686	LF	4" Double Yellow Center Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Heath Lane SUBTOTAL**	
Industrial Park Drive, T-676					
29	10	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
30	29	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, **0.3 to <3.0 million ESAL's**, SRL-M, 9.5 mm mix, 180 LB/SY		
31	6	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
32	100	LF	4" Double Yellow Center Line with Glass Beads		
33	200	LF	4" Single White Edge Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Industrial Park Drive SUBTOTAL**	

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

SCHEDULE OF PRICES
BASE BID ROADS, Continued

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
Ross Road, T-659					
34	41	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
35	123	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
36	34	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
37	560	LF	4" Double Yellow Center Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.			**Ross Road SUBTOTAL**		
Jester Court, T-721					
38	32	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
39	95	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
40	28	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
41	475	LF	4" Double Yellow Center Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.			**Jester Court SUBTOTAL**		

SEE NEXT PAGE FOR ADDITIONAL BID ROADS

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

SCHEDULE OF PRICES

ADDITIONAL BID ROADS

Hamlet Drive, T-758

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
42A	77	Tons	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
43A	232	Tons	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
44A	70	Tons	2A Crushed Aggregate, placed as Shoulder Back-Up		
45A	1,162	LF	4" Double Yellow Center Line with Glass Beads		

*DESCRIPTION
Must include ADT on Wearing surfaces.
USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.

Hamlet Drive SUBTOTAL

Geraci Place, T-720

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
46A	101	Tons	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
47A	304	Tons	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
48A	83	Tons	2A Crushed Aggregate, placed as Shoulder Back-Up		
49A	1,384	LF	4" Double Yellow Center Line with Glass Beads		

*DESCRIPTION
Must include ADT on Wearing surfaces.
USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.

Geraci Place SUBTOTAL

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

SCHEDULE OF PRICES
ADDITIONAL BID ROADS, Cont'd.

Oak Street, T-626

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
50A	37	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
51A	111	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
52A	32	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
53A	528	LF	4" Double Yellow Center Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Oak Street SUBTOTAL**	

Sharbaugh Road, T-634

1.Item No.	2. Approximate Quantities	3. Units	4.*Description	5. Unit Price	6. Total
54A	53	TONS	Superpave Asphalt Mixture Design, **Scratch/Leveling** Course, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 60 LB/SY, placed as directed		
55A	160	TONS	Superpave Asphalt Mixture Design, **Wearing Course**, PG 64S-22, 0 to 0.3 million ESAL's, SRL-M, 9.5 mm mix, 180 LB/SY		
56A	38	TONS	2A Crushed Aggregate, placed as Shoulder Back-Up		
57A	640	LF	4" Double Yellow Center Line with Glass Beads		
58A	1,280	LF	4" Single White Edge Line with Glass Beads		
*DESCRIPTION Must include ADT on Wearing surfaces. USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st and OCTOBER 31st EXCEPT AS NOTED IN BULLETIN NO. 25.				**Sharbaugh Road SUBTOTAL**	

END OF ADDITIONAL BID ROADS

ATTACHMENT #1 , Continued

County: Monroe Municipality: Coolbaugh Township Project No.: 26-45203-001

BID SUMMARY

BASE BID ROADS

Kings Way SUBTOTAL _____

Salamanca Lane SUBTOTAL_____

Echo Lake Road (1) SUBTOTAL_____

Echo lake Road (2) SUBTOTAL_____

Echo Lake Road (3) SUBTOTAL_____

Heath Lane SUBTOTAL_____

Industrial Park Drive SUBTOTAL_____

Ross Road SUBTOTAL_____

Jester Court SUBTOTAL_____

TOTAL BASE BID_____

ADDITIONAL BID ROADS

Hamlet Drive SUBTOTAL _____

Geraci Place SUBTOTAL_____

Oak Street SUBTOTAL_____

Sharbaugh Road SUBTOTAL_____

ATTACHMENT #1-A

SPECIFICATIONS AND SPECIAL PROVISIONS TO CONTRACT MS-944
CONTAINS IMPORTANT INFORMATION FOR THE CONTRACTOR
The Prime Contractor and subcontractors must comply with all of the following provisions:

TRAFFIC CONTROL

Traffic Control and Safety Devices shall be provided by the Contractor. Maintenance and protection of Traffic shall comply with the current editions of the MUTCD, PennDOT Publication 212 and PennDOT Publication 213 (Work Zone Traffic Control, Current Edition).

Full width paving in one pass may be permitted, only as agreed to by the Municipality's Road Foreman or his representative.

The Contractor may close roads where practical; all road closures must be pre-approved by the Municipality's Road Foreman or his representative. If road closures are approved, all ROAD CLOSED and DETOUR signs shall be provided by the Contractor and placed in accordance with current editions of the MUTCD, PennDOT Publication 212 and PennDOT Publication 213.

The Contractor shall place temporary centerline markings on the road directly after paving is completed. This item is incidental to the paving.

SPECIFICATIONS

GENERAL

All prospective bidders should review the project with the Township's Representative before bidding. To schedule a meeting or obtain additional information, contact Kyle Knecht, DPW/Road Foreman at 570.894.8334 or 570.656.3608 (cell).

A pre-construction meeting will be mandatory; Contractor's and all Subcontractors' on-site foremen must attend. The Contractor shall schedule this meeting with the Municipality and notify the Municipality at least 5 calendar days prior to the start of the Work.

Bidders may be either a **PennDOT Pre-qualified Prime or PennDOT Pre-qualified Subcontractor,** and proof of pre-qualification is required. Bidders must be PennDOT pre-qualified for **Work Code "F" Bituminous Paving. Proof of pre-qualification shall be provided with the bid.**

The Municipality intends to award the Contract to one bidder based on the total of the Base Bid Roads (Items 1 - 35), or of the total of the Base Bid Roads + any or all of the selected Additional Bid Roads (Items 36A - 51A). Bidders must bid on all items.

Bidders must submit their bid on documents provided by the Municipality.

Completion of a NON-COLLUSION AFFIDAVIT is required.

The successful bidder must provide a 100% Performance Bond and a 100% Payment Bond within 20 days of the Award of the Contract.

The Contractor shall verify the employment eligibility of each new employee hired after January 1, 2014, and submit the Commonwealth Public Works Employment Verification Form ("Form") included in the bid package attachments to the Municipality.

Contractor shall provide proof of CDL Drug and Alcohol Compliance upon Award of the Contract, prior to starting any work.

The Work Schedule must be coordinated with the municipality. All work must be completed on or before **September 30, 2026.** If all work is not completed by this date, Liquidated Damages will be assessed at the rate of **$975.00** per additional calendar day. **All Work under this Contract shall be done on Mondays through Fridays. No work will be permitted to take place on weekends or holidays.**

ATTACHMENT #1-A, Continued

Incidental preparation and clean-up work, including removal of any excess project construction and waste materials, shall be done by the Contractor.

Each roadway shall be power-broomed by the Contractor prior to the start of paving operations.

Delivery tickets are required for all materials used on the project, and a CS-4171 Certificate of Compliance must accompany the delivery ticket or be provided within 24 hours of delivery or placement of material on the project.

The Contractor must provide the Bill of Lading for each shipment of bituminous material in accordance with Section 702.1(c) of PennDOT Publication 408 – *Specifications*.

The Contractor must provide certified truck weight slips for bituminous material and aggregate used on this project.

No payments will be made until the Contractor has supplied all required designs, delivery slips and certifications.

Contractor shall remove any excess construction materials.

The Municipality will inspect the project.

Final Completion Certificate and Notice of Completion are required.

All quantities are approximate; the final Contract Price will be based on the actual quantities, supported with delivery tickets, as verified by the Township Road Foreman or his representative, and the bid unit prices.

Future awards of Contracts will be based on the quality of work, as determined by the Municipality.

Contractor is responsible for defects that occur within **one year** of applications.

Contractor must complete and submit CS-1PA Price Adjustment of Bituminous Material with the invoice for payment, if applicable.

All changes in the scope of work, except for minor quantity usages, must be in writing in a form acceptable to the Municipality and be pre-approved by the Municipality's Road Foreman or his representative.

This Contract authorizes the Road Foreman to approve changes in quantities up to 10% of the total bid price. Any changes in excess of 10% must be approved by the Township Board of Supervisors, or their designee.

The Municipality reserves the right to limit the amount of work completed and may adjust the amount of the paving on the Additional Bid Roads depending upon the bid prices received and projected bituminous price adjustment at the time of paving, to keep within budgetary constraints.

The Municipality further reserves the right to accept or reject any and/or all proposals, or portions thereof, to delete projects and/or portions of projects depending upon budgetary constraints, and to waive technicalities in the bidding as deemed best in the interest of the Municipality.

Completion and Scheduling of Work

If designated as the successful bidder, the Contractor may begin work on or after June 1, 2026 or as otherwise provided for in the in the Special requirements and all work must be completed by **September 30, 2026**. Some roads may be used as school bus routes. If the Contractor is performing work while school is in session, the Contractor must coordinate this work with the Municipality and will be required to contact the School District and provide the School District with a list of work locations and dates, and make provisions to accommodate bus usage of the roads.

All Work under this Contract shall be done on Mondays through Fridays. No work will be permitted to take place on weekends or holidays.

PENNSYLVANIA PREVAILING WAGES

Pennsylvania Prevailing Wages apply to this Contract. Refer to the **PREVAILING WAGES** attachment.

INSURANCE REQUIREMENTS

The awarded contractor shall purchase and maintain, at contractor's expense, during the term of this Contract, and any renewals or extensions thereof, insurance issued by companies acceptable to the Municipality. Refer to the **INSURANCE REQUIREMENTS** attachment. **Coolbaugh Township must be named as an additional insured on the policy.**

BITUMINOUS PAVING

Complete all testing in accordance with PennDOT Publication 408 – *Specifications*, Section 413.

Each roadway shall be power-broomed by the Contractor prior to the start of paving operations.

Tack Coat is required in accordance with PennDOT Publication 408 – *Specifications*, Section 460, and is incidental to paving.

Bituminous Seal is required at all abutting pavements and curbs, and is incidental to the paving.

Saw-cut or milled paving notches are required at all abutting pavements, including paved driveways and approaches, and are incidental to the paving. Contractor is responsible for the removal and proper disposal of milled materials. **See MILLING Section, below.**

Milling at driveways is to be done as directed by the Municipality in a manner that maintains the shoulder slope and provides a smooth transition from the driveways to the shoulder, and is incidental to the paving. **See MILLING Section, below.**

Contractor shall provide PennDOT approved bituminous mix design conforming to the requirements and standards of PennDOT Publication 408 – *Specifications* to the Municipality at least 5 days prior to the start of work.

A Bill of Lading shall be provided to the Municipality for each shipment of bituminous material in accordance with PennDOT Publication 408 – *Specifications*, Section 702.1(c). **This shall include tack oil.**

Bituminous Delivery tickets must contain the Job Mix Number (CAMMS No.) from the appropriate bituminous design. This shall include tack oil.

Bituminous Material Certifications must contain the Job Mix Number (CAMMS No.) from the appropriate bituminous design. This shall include tack oil.

The finished cross-section roadways shall have a uniform crown of ¼ inch per foot, subject the tolerances of PennDOT Publication 408 – *Specifications*, except where superelevated, or where otherwise directed.

MILLING

- The Contractor shall perform the milling of pavement and driveway notches as directed, as incidental to the paving. Milled material is the property of the Township; the Contractor shall be responsible for hauling the milled material to a designated site within Coolbaugh Township, which shall be considered incidental to the milling.

- **All driveways along paved roads must be milled back a minimum of 2' from the edge of pave, or as otherwise directed by the Township's Representative.**

ATTACHMENT #1-A, Continued

9.5 MM SCRATCH/LEVELING COURSE

The scope of this work is the construction of a paver-placed Bituminous Scratch/Leveling Course, as directed by the Municipality's representative, over an existing bituminous roadway to correct rutting, to fill in low areas and correct other similar problems, and includes miscellaneous road preparation, milling of pavement notches and driveways (milling to include removal and proper disposal of milled materials), tack coating (in accordance with PennDOT Publication 408 – *Specifications*, Section 460) where material is not placed over newly placed bituminous material, and sealing of joints and utilities; all of these items are incidental to the paving. The Municipality may direct the contractor to place hand or machine-placed roll bituminous curb; placement of this curb shall be included in the paving cost. Use of a rubber-tired roller is required for Scratch/Leveling Courses. All materials and workmanship shall conform to the standards and requirements of PennDOT Publication 408 – *Specifications*. Full width paving in one pass may be permitted, only as agreed to by the Municipality's Road Foreman or his representative.

9.5MM WEARING COURSE

The scope of this work is the construction of a 180 LB/SY (1½" depth) paver-placed Bituminous Wearing Course using the material indicated in the Schedule of Prices over an existing bituminous roadway surface or over a newly placed Scratch/Leveling Course. Placement includes miscellaneous road preparation, milling of pavement notches at intersection roads and driveways, and milling at bridge approaches as directed (milling to include removal and proper disposal of milled materials), tack coating (in accordance with PennDOT Publication 408 – *Specifications*, Section 460) where material is not placed over newly placed bituminous material, and sealing of joints and utilities; all of these items are incidental to the paving. The Municipality may direct the Contractor to place hand or machine placed roll bituminous curb and/or safety edges which, if required, are also incidental to the paving. All materials and workmanship shall conform to the standards and requirements of PennDOT Publication 408 – *Specifications*. Full width paving in one pass may be permitted, only as agreed to by the Municipality's Road Foreman or his representative.

SHOULDER BACK-UP

The scope of this work is to construct shoulders adjacent to all newly paved areas, where safety edges are not required, to back-up the newly paved areas to the approximate width of the existing shoulders and to the depth required to the top of the pavement. Shoulders shall have a uniform slope of approximately 1/2" to 3/4" per foot away from the pavement. This work shall be done in accordance with PennDOT Publication 408 – *Specifications,* Section 350 – Subbase, using 2A Crushed Aggregate meeting the requirements of PennDOT Publication 408 – *Specifications*, Section 703.2 for Type C or better material. Placement shall be done with an adjustable shoulder machine, designed and constructed for the purpose, capable of placing and screeding the aggregate without segregation. Compaction of the Crushed Aggregate Shoulder shall be done in accordance with the requirements of PennDOT Publication 408 – *Specifications,* Section 350.3.

LINE PAINTING

The scope of work is the supply all materials, equipment and labor to apply double 4" yellow center traffic lines and single white edge lines (where listed) with glass beads to all included roadways and to properly control traffic and conform to PennDOT Publication 212 and 213. The material and work shall conform to PennDOT Publication 408, Section 962.

The Contractor shall obtain all materials from an approved PENNDOT Bulletin 15 supplier and provide Certification as specified in PennDOT Pub 408, Section 106.03(b)3, that the paint and glass beads meet the following specifications:

- Glass Beads: Conforming to Current PennDOT Publication 408, Section 1103.14 meeting "Type A" Gradation.
- Paint: Provide the correct color and type of waterborne paint from a source listed in Bulletin 15.

ATTACHMENT #1-A, Continued

Price Adjustment of Bituminous Materials (Escalator Clause)

The quantities of bituminous material bid in this contract contains sufficient asphalt cement so that the bituminous price adjustment specified in PennDOT Publication 408 - *Specifications*, Current Edition, Section 110.04 Price Adjustment of Bituminous Materials will apply. When the bituminous material used or indicated for placement exceeds the 100 ton threshold, then a bituminous price adjustment will be allowed as per PennDOT Publication 408 - *Specifications*, Current Edition, Section 110.04 Price Adjustment of Bituminous Materials. If the bituminous material incorporates RAP or RAS in the mix design the 100 ton limit and the bituminous price adjustment will only be calculated on the virgin asphalt. The Base Bid Price Index (IB) will be calculated using the month in which the project is first advertised and the work is in the applicable Zone. The Bidder will be responsible for completing a CS-1PA Price Adjustment of Bituminous Materials calculation form if applicable. The bidder will provide this form with the invoices and the invoices will show the per ton or per SY price in the bid and the lump sum price increase or decrease supported with CS-1PA calculation form. The bidder shall also supply the Municipality with a copy of the bituminous mix design for each material supplied with the initial CS-1PA form or if the bituminous mix design changes. If the contract goes beyond the **September 30, 2026** completion date, the Contractor shall not be able to pass on any additional cost for any material placed beyond the month of **September**. Any material placed after **September 30, 2026**, shall only be subject to the bituminous price adjustment for **September 30, 2026**, unless the bituminous price adjustment falls, then the bituminous price adjustment applicable at that time shall be calculated for material placed after **September 30, 2026**. **Prior to the start of the work the bidder shall provide the Municipality with the per ton or per SY calculation of the bituminous price adjustment.**

APPLICATIONS AND ESTIMATED QUANTITIES

Applications and estimated quantities for each road are listed above. The Township Roadmaster or his representative will instruct the Contractor as to what work is to be done on each road. Measurements and calculations of quantities are for bidding purposes only, final measurements will be conducted by a representative from the Contractor and a representative from the Municipality and final payment will be based on these mutually agreed to measurements and quantities.

My signature signifies that I have read and understand the above conditions and special provisions to this contract, and by being authorized by this company to act as their authorized representative, and on their behalf hereby agree to adhere to any and all of the provisions pertaining to this contract.

_____	_____
Contractor's Representative Date	**Municipality's Representative Date**
_____	_____
Company	**Municipality**

ATTACHMENT #1-B
LOCATION AND DESCRIPTION OF WORK

BASE BID ROADS

Kings Way, T-715 from 235' in from SR 196 to Rob Roy Dr.		1,761' x 22'	4,305 SY
(0.0 to < 0.3 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	129 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	387 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	106 Tons		
4" Double Yellow Centerline with Glass Beads	1,761 LF		
4" Single White Edge Line with Glass Beads	3,522 LF		
Salamanca Lane, T-655 from Hemlock Dr. to Seneca Way		2,767' x 20'	6,149 SY
(0.0 to <0.3 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	184 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	553 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	166 Tons		
4" Double Yellow Centerline with Glass Beads	2,767 LF		
Echo Lake Road, T-591 (1) from Lake Rd. to Paupack Ln.		3,640' x 26'	10,516 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	315 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	946 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	218 Tons		
4" Double Yellow Centerline with Glass Beads	3,640 LF		
4" Single White Edge Line with Glass Beads	7,280 LF		
Echo Lake Road, T-591 (2) from Long Woods Rd. to Cayuga Dr.		1,531' x 26'	4,423 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	133 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	398 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	92 Tons		
4" Double Yellow Centerline with Glass Beads	1,531 LF		
4" Single White Edge Line with Glass Beads	3,062 LF		
Echo Lake Road, T-591 (3) from Keystone Ln. to Laurel Dr.		970' x 26'	2,802 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	84 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	252 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	58 Tons		
4" Double Yellow Centerline with Glass Beads	970 LF		
4" Single White Edge Line with Glass Beads	1,940 LF		

ATTACHMENT #1-B, Continued
LOCATION AND DESCRIPTION OF WORK

BASE BID ROADS, Continued

Heath Lane, T-645 from SR 940 to Twp/Boro Line		686' x 22'	1,677 SY
(0.0 to <0.3 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	50 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	151 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	41 Tons		
4" Double Yellow Centerline with Glass Beads	686 LF		

Industrial Park Drive, T-676 from Twp/Boro Line for 100'		100' x 29'	322 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	10 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	29 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	6 Tons		
4" Double Yellow Centerline with Glass Beads	100 LF		
4" Single White Edge Line with Glass Beads	200 LF		

Ross Road, T-659 from Sussex Dr. to Drexel Rd.		560' x 22'	1,369 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	41 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	123 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	34 Tons		
4" Double Yellow Centerline with Glass Beads	560 LF		

Jester Court, T-721 from Victoria Dr. to Renaissance Ln.		475' x 20'	1,056 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	32 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	95 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	28 Tons		
4" Double Yellow Centerline with Glass Beads	475 LF		

SEE NEXT PAGE FOR ADDITIONAL BID ROADS

ATTACHMENT #1-B, Continued
LOCATION AND DESCRIPTION OF WORK

ADDITIONAL BID ROADS

Hamlet Drive, T-758 from Falstaff Dr. to Horatio Rd.		1,162' x 20'	2,582 SY
(0.0 to <0.3 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	77 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	232 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	70 Tons		
4" Double Yellow Centerline with Glass Beads	1,162 LF		

Geraci Place, T-720 from Renaissance Ln. to Leslie Way		1,384' x 22'	3,383 SY
(0.0 to <0.3 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	101 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	304 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	83 Tons		
4" Double Yellow Centerline with Glass Beads	1,384 LF		

Oak Street, T-626 from Main St. to Goodwin St.		528' x 21'	1,232 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	37 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	111 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	32 Tons		
4" Double Yellow Centerline with Glass Beads	528 LF		

Sharbaugh Road, T-634 from SR 611 to Hemlock Dr.		640' x 25'	1,778 SY
(0.3 to <3.0 million ESAL's, SRL-M)			
60# 9.5 mm Scratch/Leveling Course	53 Tons		
1½" (180 LB/SY) 9.5 mm Wearing Course	160 Tons		
2A Crushed Aggregate Placed as Shoulder Back-Up	38 Tons		
4" Double Yellow Centerline with Glass Beads	640 LF		
4" Single White Edge Line with Glass Beads	1,280 LF		

APPLICATIONS AND ESTIMATED QUANTITIES

Applications and estimated quantities for each road are listed above. The Township Roadmaster or his representative will direct the Contractor as to the work to be done on each road. Measurements and calculations of quantities are for bidding purposes only; final measurements will be conducted by a representative from the Municipality and from the Contractor, and final payment will be based on these mutually agreed to measurements and the actual quantities of materials based on certified delivery slips.

PROPOSAL AND CONTRACT INSTRUCTIONS – FORM 944

1. The proposal must be typewritten or printed.

2. If more than one proposal on any project is submitted by any individual, firm or partnership, corporation or association under the same names, only one lowest proposal will be considered.

3. Description of work------

   A. If additional space is needed, insert appropriately numbered attachment and note, "Continued on Attachment No. _____."

   B. Where Wearing Surfaces are a part of this Contract, Average Daily Traffic (ADT) Count or SRL determination must be included in the description.

4. Part A of Page 1 to be completed by municipality. Part B of Page 1 to be completed by contractor. Schedule of Prices – Column #1 (Item), #2 (Approximate Quantities), #3 (Unit, i.e., ton, square yard, linear feet, etc.) and #4 (Description, i.e., bituminous materials – ID-2, FJ1, FB1, BCBC, etc.) must be filled in by the municipality to insure equitable bidding. Column #5 (Unit Price), #6 (Total), and total amount of bid must be filled in by the contractor. If more space is needed, add note at bottom of the page: Continued on Attachment No. 1-A," and add additional sheet designated as Attachment No. 1-A, 1-B, etc. Repeat for each additional sheet required.

5. If liquidated damages are to be assessed, add the following sentence to Part A #2. "If all work is not completed on time, liquidated damages will be assessed at the rate of $ _____per additional working day." (OR…as set forth in the attached schedule.")

6. Payment and Performance bonds are provided only by the successful bidder. Contracts under $5,000 – bonds must be in 50% of the contract amount. Contracts in excess of $5,000 – bonds must be in 100% of the contract amount. Bond Form MS-944 Attachments 2 and 3 and Workmen's Compensation Affidavit Attachment 4 must be submitted by the successful bidder within 20 days of the contract award. Failure to submit the bonds shall constitute grounds to cancel the contract.

7. *Construction projects, where the estimated cost of the total project exceeds $25,000, are subject to the provisions of the Pennsylvania Prevailing Wage Act 442. It is the responsibility of the municipality to obtain the Prevailing Wage Scale for the area and include it in the proposal. IF the Prevailing Wage Act applies, this fact shall be noted in the advertisement.

   On projects utilizing Federal Revenue Sharing Funds, if the project cost exceeds $2,000 and is financed with 25% or more Federal Revenue Sharing Funds, the Davis Bacon Act applies. Again, it is the responsibility of the municipality to obtain the Davis Bacon Wage Rates, include them in the proposal and note the fact in the advertisement. If both Acts are applicable, the Davis Bacon Act has preference over the Pennsylvania Prevailing Wage Act.

8. An ESCALATOR CLAUSE is optional; however, if used, it must be included in the proposal prepared by the municipality. An escalator clause may not be inserted by the contractor.

*(1961, Aug. 15, P.L. 987; 43 P.S. 165)

PERFORMANCE BOND
(With Corporate Surety)

KNOW ALL MEN BY THESE PRESENTS, that we, _____
(NAME AND ADDRESS OF CONTRACTOR)

_____

as Principal and _____
(SURETY COMPANY)

a corporation incorporated under the laws of the State of _____as Surety
(NAME OF STATE)

are held and firmly bound unto _____ . In the full and just sum

of _____ ($ _____) dollars

lawful money of the United States of America, to be paid to the above Municipality or its assigns, to which payment well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly and severally, firmly by these presents.

WHEREAS, the above bound Principal has entered into a contract with the above Municipality, bearing even date herewith, for the undertaking of certain obligations as therein set forth.

NOW, THEREFORE, the condition of this obligations such that if the bounden Principal, as Contractor, shall in all respects comply with and faithfully perform the terms and conditions of said Contract, including the Specifications and conditions referred to and made a part thereof, and such alterations as may be made in said Specifications as therein provided, and shall well and truly, and in a manner satisfactory to the Municipality fulfill all obligations as therein set forth, then this Obligation shall be void, but otherwise the same shall be and remain in full force, virtue and effect.

It is further provided that any alteration which may be made in the terms of the contract or its specifications with the express approval of the Municipality or the Principal to the other, shall not in any way release the Principal and Surety or either or any of them, their heirs, executors, administrators, successors or assigns from their liability hereunder, notice to the Surety of any such alteration or forbearance being hereby waived.

IN WITNESS WHEREOF, the said Principal and Surety have duly executed this Bond under Seal, pursuant to

due and legal action authorizing the same to be done on _____
(DATE OF BOND)

SEAL

Attest / Witness

_____
CONTRACTOR

_____ BY:_____
TITLE TITLE

SEAL

Attest / Witness

_____
SURETY COMPANY

_____ BY:_____
TITLE TITLE

KNOW ALL MEN BY THESE PRESENTS, that we, _____

of _____, as PRINCIPAL and _____

corporation incorporated under the laws of the State of _____as SURETY, are

held and firmly bond unto the _____, in the full and just sum of

_____ ($ _____) dollars, lawful money of the United

States of America, to be paid to the said _____ or its assigns, to which payment well and true to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the above bounden Principal has entered into a contract with the above municipality, hereinafter called Obligee, bearing even date herewith, for the improvement of a certain section of highway or bridge in said Municipality consisting of: _____

---

for approximately the sum of _____ ($ _____) dollars.

NOW, THEREFORE, the condition of this obligation is such that if the above bounden PRINCIPAL shall and will promptly pay or cause to be paid in full all sums of money which may be due to contract or otherwise, to any individual, firm, partnership, association or corporation, for all material furnished or labor supplied or performed in the prosecution of the work, whether or not the said material or labor entered into and became component parts of the work and for rental of the equipment used and services rendered by public utilities in, or in connection with the prosecution of such work, then this obligation to be void, otherwise to remain in full force and effect.

The PRINCIPAL and SURETY, hereby, jointly and severally, agree with the Obligee herein that any individual firm, partnership, association or corporation, which has performed labor or furnished material in the prosecution of the work as provided, and any public utility which has not been paid in full therefore, may sue in assumpsit's on this Payment bond in his, them or it, and have execution thereon. Provided, however, that the Obligee shall not be liable for the payment of any costs of expenses of such suit.

RECOVERY by any individual, firm, partnership, association or corporation hereunder shall be subject to the provisions of the "Public Works Contractors' Bond Law of 1967", Act No. 385, approved December 20, 1967, P.L. 869, which Act shall be incorporated herein and made a part hereof, as fully and completely as though its provisions were fully and at length herein recited.

It is further provided that any alterations which may be made in the terms of the contract or in the work to be done or materials to be furnished or labor to be supplied or performed under it or the giving by the Obligee of any extension or forbearance being hereby waived.

IN WITNESS WHEREOF, the said PRINCIPAL and SURETY have duly executed this Bond under seal this _____Day of _____, 20 _____.

WITNESS:

_____
CONTRACTOR

_____ BY:_____
TITLE TITLE

WITNESS:

_____
SURETY COMPANY

_____ BY: _____
TITLE TITLE

AFFIDAVIT RE
ACCEPTING PROVISIONS OF THE WORKMEN'S COMPENSATION ACT

State of)
)
)SS:
)
County of)

Being duly sworn according to law deposes and says that they have / he has / it accepted the provisions of the Workmen's Compensation Act of 1915 of the Commonwealth of Pennsylvania, with its supplements and amendments, and have insured their liability hereunder in it accordance with the terms of said Act with _____
(SURETY COMPANY)

_____
(TYPE OR PRINT) CONTRACTOR

BY: _____
SIGNATURE

Sworn to and subscribed before me this _____ day of _____A.D. 20 _____

My Commission Expires _____
(DATE)

D-7126 (6-99)

ANTI-COLLUSION AFFIDAVIT

County Monroe

Municipality Coolbaugh Township

Project Number 26-45203-001

State of _____ Fed. Project No. _____
(If Applicable)

County of _____

The undersigned deponent deposes and says that he is the _____

of the _____Company; that he is authorized to make this affidavit on behalf of said company in compliance with section 102.06 (e) of Department Specifications, Publication 408, as amended and that the said company has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with such contract.

_____
(Contractor)

BY

_____

Sworn to and subscribed before me the undersigned notary public this

_____ **day of** _____**,** _____**.**

_____
Notary Public

My Commission expires _____

CS-1PA REV(10-00)	**PRICE ADJUSTMENT OF BITUMINOUS MATERIAL (ENGLISH)**	CMS NO. PAGE NO. ATTACH SR / SEC.	26-45203-001

ITEM NO.: _____ MONTH PLACED: _____

GALLON _____ TON _____ SQ.YARD _____

IP = PRICE INDEX FOR MONTH MATERIAL WAS PLACED =
IB = PRICE INDEX IN THE BID PROPOSAL =
IP / IB =

WHEN THE RATIO IP/IB FALLS WITHIN THE RANGE OF 0.90 TO 1.10 **NO PRICE ADJUSTMENT** IS NEEDED
WHEN THE RATIO IP/1B IS CALCULATED TO BE LESS THAN 0.90 , THE DEPT. WILL RECEIVE A **PRICE REBATE**
WHEN THE RATIO IP/IB IS CALCULATED TO BE GREATER THAN 1.10 , THE CONTRACTOR WILL RECEIVE A **PRICE INCREASE**

MATERIAL PLACED:

DATE	GALLON
TOTAL	

DATE	TON
TOTAL	

DATE	SQ.YARD
TOTAL	

GALLON BASIS:

BITUMINOUS TONNAGE (Q) = 0.004164 x SPEC.GRAV. OF BIT. MAT. x % ASPHALT IN EMULSION x NO. OF GALLONS
SPECIFIC GRAVITY OF BIT. MAT. =
% ASPHALT IN EMULSION =
NO. OF GALLONS =
Q =

GALLONS PER SQUARE YARD BASIS:

BITUMINOUS TONNAGE (Q) = 0.004164 x AREA (SY) x APPL. RATE (Gallons / SY) x SPEC.GRAV. OF BIT.MAT.
ACTUAL RESIDUE APPL. RATE =
SPECIFIC GRAVITY OF BIT. MAT. =
SURFACE AREA =
Q =

SQUARE YARD BASIS:

BIT. MIX. TONNAGE PLACED = 0.000375 x AREA (SY) x DESIGN DEPTH (inches) x DESIGN DENSITY (lb / ft3)
DESIGN DEPTH =
DESIGN DENSITY* =
SURFACE AREA =
BIT. MIX. TONNAGE PLACED =
BITUMEN TONNAGE (Q) = BIT. MIXTURE TONNAGE PLACED x % BITUMEN BY WEIGHT
% BITUMEN BY WEIGHT* =
Q =

*DESIGN DENSITY AND % BITUMEN TO BE OBTAINED FROM FORM TR-448A. DENSITY OF WATER = 62.4 lb / ft3.

TONNAGE BASIS:

BITUMEN TONNAGE (Q) = BIT. MIXTURE TONNAGE PLACED x % BITUMEN BY WEIGHT
% BITUMEN BY WEIGHT* =
BIT. MIXTURE TONNAGE =
Q =

*% BITUMEN TO BE OBTAINED FROM FORM TR-448A.

PRICE INCREASE = (IP / IB - 1.10) x BITUMEN TONNAGE (Q) x IB
= (- 1.10) x ( ) x ( ) =

PRICE REBATE = (0.90 - IP / IB) x BITUMEN TONNAGE (Q) x IB
= (0.90 -) x ( ) x ( ) =

MUNICIPALITY Coolbaugh Township

NOTICE OF COMPLETION

IN REFERENCE TO PROJECT # 26-45203-001

Name of Contractor _____

Performance of work as specified on the above numbered contract is completed and final pavement inspection has been made by the contractor and municipality in accordance with the terms of the contract awarded.

DATE OF AWARD: _____

_____
Signature of Municipality

_____
Signature of Contractor

Both copies of this form to be filled by the Contractor-Municipality on completion of final pavement restoration.

THIS PORTION TO BE COMPLETED BY MUNICIPALITY

FINAL COMPLETION CERTIFICATE

By the affixing of my signature, I hereby certify that final inspection has been made and all work has been performed in accordance with the above contract # and is hereby accepted by the municipality as completed.

_____
Authorized Agent for the Municipality

*DATE: _____

*** The Bidder is responsible for maintenance of permanent pavement repairs for a period of one year from this date.**

INSURANCE REQUIREMENTS

The awarded Contractor shall purchase and maintain, at its expense, during the term of this contract and any renewals or extensions thereof, the following types of insurance issued by companies acceptable to the Municipality.

1. Workmen's compensation insurance sufficient to cover all of the employees of the contractor working to perform this contract, as required by the laws of the Commonwealth.

2. Comprehensive general liability insurance, property damage insurance, and where appropriate automobile liability insurance. The minimum amount of coverage shall be $250,000.00 per person and $1,000,000.00 per occurrence for bodily injury, including death and $250,000.00 per person and $1,000,000.00 per occurrence for property damage.

These coverages shall be occurrence-based. **The policy shall name the Municipality as an additional insured** and shall contain a provision that the coverages afforded thereunder shall not be cancelled or changed unless at least thirty (30) days prior written notice has been given to the Municipality.

Prior to the commencement of work, the Contractor shall provide the Municipality with a current certificate(s) of insurance showing the required coverages and provisions.

3. Your attention is directed to the hold harmless and indemnification provision:
"The Contractor shall hold the Municipality harmless from any indemnify the Municipality against any and all claims, demands, and actions based upon or arising out of any activities performed by the Contractor and its employees and agents under this Contract and shall, at the request of the Municipality, defend any and all actions brought against the Municipality based upon any such claims or demands."

PUBLIC WORK EMPL0YMENT VERIFICATION ACT

Provision Body

PUBLIC WORK EMPLOYMENT VERIFICATION ACT

General. In accordance with Act 127 of 2012, known as the Public Works Employment Verification Act ("the Act"), effective January 1, 2014, 43 P.S. §§167.1-167.11, the Contractor shall use the Federal Government's E-Verify system to ensure that all employees performing work on the project, including subcontractor's employees, are authorized to work in the United States.

Verification Form. The Contractor shall verify the employment eligibility of each new employee hired after January 1, 2013 and submit the Commonwealth Public Works Employment Verification Form ("Form") included in the bid package attachments to the Municipality.

Contractor. Mail the Form, signed by an authorized representative of the Contractor to the Municipality along with the Performance and Payment Bonds as specified by the contract documents. Failure or refusal to provide the Form will be considered a refusal to comply with bidding requirements, will result in rejection of the bid, and may subject the Contractor to the enforcement activities, sanctions and civil penalties specified in the Act.

Subcontractor. The Prime Contractor will obtain a Form signed by an authorized representative of any subcontractor performing work on the project, possessing sufficient knowledge to make the representations and certifications on the Form. The Prime Contractor shall submit the Form to the Municipality prior to requesting subcontractor approval and before the subcontractor performs any work. Failure or refusal to provide the Form will be considered a refusal to comply with subcontractor approval requirements, will result in rejection of the subcontractor request, and may subject the subcontractor to the enforcement activities, sanctions and civil penalties specified in the Act.
The Prime Contractor shall include information about the requirements of the Act in all subcontracts.

Department of General Services. The Department of General Services is the Commonwealth agency responsible for enforcement and administration of the Act. Please direct questions about the Act to:
Department of General Services Public Works
Employment Verification Compliance Office
Room 105 Tent Building
18th and Herr Streets
Harrisburg, PA 17125
Fax: 717-214-3669

COMMONWEALTH OF PENNSYLVANIA

PUBLIC WORKS EMPLOYMENT VERIFICATION FORM

Date_____

Business or Organization Name (Employer) _____

Address _____

City _____ State _____ Zip Code _____

____ Contractor ____ Subcontractor (Check One)

Contracting Public Body: _____

Contract/Project No.: ____26-45203-001_____

Project Description: _____

Project Location: _____

As a contractor/subcontractor for the above referenced public works contract, I hereby affirm that as of the above date, our company is in compliance with the Public Works Employment Verification Act ('the Act') through utilization of the federal E-Verify Program (EVP) operated by the United States Department of Homeland Security. To the best of my/our knowledge, all employees hired post January 1, 2013 are authorized to work in the United States.

It is also agreed to that all public works contractors/subcontractors will utilize the federal EVP to verify the employment eligibility of each new hire within five (5) business days of the employee start date throughout the duration of the public works contract. Documentation confirming the use of the federal EVP upon each new hire shall be maintained in the event of an investigation or audit.

I, _____, authorized representative of the company above, attest that the information contained in this verification form is true and correct and understand that the submission of false or misleading information in connection with the above verification shall be subject to sanctions provided by law.

_____
Authorized Representative Signature

PREVAILING WAGES ATTACHMENT

GENERAL CONDITIONS FOR PREVAILING WAGES

A. All Bidders must comply with, but not limited to, the following requirements:

1. The general prevailing minimum wage rates including contributions for employee benefits as determined by the Secretary which shall be paid to the workmen employed in the performance of the contract. The contractor shall pay at least the wage rates as determined in the decision of the Secretary of Labor and Industry contained in the Project Manual and shall comply with the conditions of the act approved August 15, 1961, and the regulations issued thereto, to assure the full and proper payment of the rates.

2. Workmen shall be paid at least the general prevailing minimum wage rates and other provisions to assure payment thereof as set forth in this section.

3. The provisions apply to work performed on the contract by the contractor and to work performed on the contract by subcontractors.

4. The contractor shall insert in each of his subcontracts the stipulations contained in these required provisions and other stipulations as may be required.

5. The contract shall provide that no workmen may be employed on the public work except in accordance with the classifications in the decision of the Secretary. If additional or different classifications are necessary the procedure in § 9.107 (relating to petition for review of rates and hearings) shall be followed.

6. Workmen employed or working on the public work shall be paid unconditionally, regardless of whether a contractual relationship exists or the nature of a contractual relationship which may be alleged to exist between a contractor, subcontractor and workmen, at least once a week, without deduction or rebate, on any account, either directly or indirectly except authorized deductions, the full amounts due at the time of payment, computed at the rates applicable to the time worked in the appropriate classification. Nothing in the contract, the act or this title prohibits the payment of more than the general prevailing minimum wage rates as determined by the Secretary to a workman on public work.

7. The contractor and each subcontractor shall post for the entire period of construction the wage determination decisions of the Secretary, including the effective date of changes thereof, in a prominent and easily accessible place or places at the site of the work and at the places used by them to pay workmen their wages. The posted notice of wage rates shall contain the following information:

(i) The name of project.
(ii) The name of the public body for which it is being constructed.
(iii) The crafts and classifications of workmen listed in the Secretary's general prevailing minimum wage rate determination for the particular project.
(iv) The general prevailing minimum wage rates determined for each craft and classification and the effective date of changes.

PREVAILING WAGES ATTACHMENT

(v) A statement advising workmen that if they have been paid less than the general prevailing minimum wage rate for their job classification or that the contractor or subcontractor are not complying with the act or this title, they may file a protest in writing with the Secretary within 3 months of the date of the occurrence, objecting to the payment to a contractor to the extent of the amount due or to become due to them as wages for work performed on the public work project. A workman paid less than the rate specified in the contract shall have a civil right of action for the difference between the wage paid and the wages stipulated in the contract, which right of action shall be exercised within 6 months from the occurrence of the event creating the right.

8. The contractor and subcontractors shall keep an accurate record showing the name, craft or classification, number of hours worked per day and the actual hourly rate of wage paid, including employee benefits, to each workman employed by him in connection with the public work. The record shall include deductions from each workman. The record shall be preserved for 2 years from the date of payment and shall be open at reasonable hours to the inspection of the public body awarding the contract and to the Secretary or his authorized representatives.

9. Apprentices shall be limited to numbers in accordance with a bona fide apprenticeship program registered with and approved by The Pennsylvania Apprenticeship and Training Council and only apprentices whose training and employment are in full compliance with The Apprenticeship and Training Act (43 P. S. §§ 90.1 - 90.10), approved July 14, 1961, and the regulations issued thereto shall be employed on the public work project. A workman using the tools of a craft who does not qualify as an apprentice within this subsection shall be paid the rate predetermined for journeymen in that particular craft or classification.

10. Wages shall be paid without deductions except authorized deductions. Employers not parties to a contract requiring contributions for employee benefits which the Secretary has determined to be included in the general prevailing minimum wage rate shall pay the monetary equivalent thereof directly to the workmen.

11. Payment of compensation to workmen for work performed on public work on a lump sum basis, or a piece work system, or a price certain for the completion of a certain amount of work, or the production of a certain result shall be deemed a violation of the act and this subchapter, regardless of the average hourly earnings resulting therefrom.

12. Each contractor and each subcontractor shall file a statement each week and a final statement at the conclusion of the work on the contract with the contracting agency, under oath, and in form satisfactory to the Secretary, certifying that workmen have been paid wages in strict conformity with the provisions of the contract as prescribed by this section or if wages remain unpaid to set forth the amount of wages due and owing to each workman respectively.

13. The provisions of the act shall be incorporated by reference in the contract. The full text of regulations for the prevailing wage act can be obtained on the Pennsylvania Department of Labor and Industry web site (http://www.dli.state.pa.us).

PREVAILING WAGES ATTACHMENT

INSERT

PREVAILING

WAGES

HERE

BUREAU OF LABOR LAW COMPLIANCE
PREVAILING WAGES PROJECT RATES

Project Name:	Coolbaugh Township 2026 Bituminous Road Paving
General Description:	Bituminous pavement overlays, stone shoulder surfacing, and highway line painting on approximately 2.4 miles of various township roads.
Project Locality	Coolbaugh Township
Awarding Agency:	Coolbaugh Township Board of Supervisors
Contract Award Date:	5/18/2026
Serial Number:	26-03451
Project Classification:	Highway
Determination Date:	4/8/2026
Assigned Field Office:	Scranton
Field Office Phone Number:	(570)963-4577
Toll Free Phone Number:	(877)214-3962
Project County:	Monroe County

BUREAU OF LABOR LAW COMPLIANCE
PREVAILING WAGES PROJECT RATES

Project: 26-03451 - Building	Effective Date	Expiration Date	Hourly Rate	Fringe Benefits	Total
Asbestos & Insulation Workers	7/1/2025		$37.08	$28.17	$65.25
Boilermaker (Commercial, Institutional, and Minor Repair Work)	3/1/2024		$36.71	$19.13	$55.84
Boilermaker (Commercial, Institutional, and Minor Repair Work)	3/1/2026		$41.34	$19.23	$60.57
Boilermakers	1/1/2024		$52.10	$35.72	$87.82
Boilermakers	1/1/2026		$58.00	$36.57	$94.57
Bricklayers, Stone Masons, Pointers, Caulkers, Cleaners	5/4/2025		$40.14	$22.07	$62.21
Bricklayers, Stone Masons, Pointers, Caulkers, Cleaners	5/3/2026		$41.99	$22.07	$64.06
Carpenters - Piledriver/Welder	1/1/2025		$43.38	$22.72	$66.10
Carpenters - Piledriver/Welder	1/1/2026		$44.63	$23.47	$68.10
Carpenters, Drywall Hangers, Framers, Instrument Men, Lathers, Soft Floor Layers	5/1/2025		$36.57	$20.29	$56.86
Carpenters, Drywall Hangers, Framers, Instrument Men, Lathers, Soft Floor Layers	5/1/2026		$36.57	$22.29	$58.86
Carpenters, Drywall Hangers, Framers, Instrument Men, Lathers, Soft Floor Layers	5/1/2027		$36.57	$24.29	$60.86
Carpenters, Drywall Hangers, Framers, Instrument Men, Lathers, Soft Floor Layers	5/1/2028		$36.57	$26.29	$62.86
Cement Finishers & Plasterers	5/4/2025		$33.66	$22.42	$56.08
Cement Finishers & Plasterers	5/3/2026		$35.66	$22.42	$58.08
Cement Finishers & Plasterers	5/3/2027		$34.92	$25.16	$60.08
Cement Masons	6/1/2024		$37.78	$15.05	$52.83
Drywall Finisher	5/1/2025		$33.24	$25.08	$58.32
Electricians	6/2/2025		$65.43	$42.20	$107.63
Electricians	6/1/2026		$67.92	$43.81	$111.73
Electricians	5/31/2027		$70.29	$45.34	$115.63
Elevator Constructor	1/1/2025		$61.41	$44.95	$106.36
Elevator Constructor	1/1/2026		$64.06	$46.01	$110.07
Glazier	5/1/2024		$39.48	$23.81	$63.29
Iron Workers (Bridge, Structural Steel, Ornamental, Precast, Reinforcing)	7/1/2025		$38.76	$33.38	$72.14
Laborers (Class 01 - See notes)	5/1/2025		$32.09	$20.14	$52.23
Laborers (Class 01 - See notes)	5/1/2026		$33.09	$20.79	$53.88
Laborers (Class 02 - See notes)	5/1/2025		$33.12	$20.14	$53.26
Laborers (Class 02 - See notes)	5/1/2026		$34.12	$20.79	$54.91
Laborers (Class 03 - See notes)	4/27/2025		$32.74	$20.14	$52.88
Laborers (Class 03 - See notes)	5/1/2026		$33.74	$20.79	$54.53
Laborers (Class 04 - See notes)	4/27/2025		$34.24	$20.14	$54.38
Laborers (Class 04 - See notes)	5/1/2026		$35.24	$20.79	$56.03
Laborers (Class 05 - See notes)	5/1/2025		$34.09	$20.14	$54.23
Laborers (Class 05 - See notes)	5/1/2026		$35.09	$20.79	$55.88
Laborers (Class 06 - See notes)	5/1/2025		$33.44	$20.14	$53.58
Laborers (Class 06 - See notes)	5/1/2026		$34.44	$20.79	$55.23
Marble Mason	5/1/2025		$36.57	$21.69	$58.26

BUREAU OF LABOR LAW COMPLIANCE
PREVAILING WAGES PROJECT RATES

Project: 26-03451 - Building	Effective Date	Expiration Date	Hourly Rate	Fringe Benefits	Total
Marble Mason	5/1/2026		$38.52	$21.69	$60.21
Millwright	6/1/2025		$43.00	$22.95	$65.95
Millwright	6/1/2026		$44.97	$22.95	$67.92
Operators (Building, Class 01 - See Notes)	5/1/2025		$44.89	$30.92	$75.81
Operators (Building, Class 01 - See Notes)	5/1/2026		$46.05	$31.76	$77.81
Operators (Building, Class 01A - See Notes)	5/1/2025		$47.14	$31.58	$78.72
Operators (Building, Class 01A - See Notes)	5/1/2026		$48.30	$32.42	$80.72
Operators (Building, Class 02 - See Notes)	5/1/2025		$44.61	$30.83	$75.44
Operators (Building, Class 02 - See Notes)	5/1/2026		$45.77	$31.67	$77.44
Operators (Building, Class 02A - See Notes)	5/1/2025		$46.86	$31.50	$78.36
Operators (Building, Class 02A - See Notes)	5/1/2026		$48.02	$32.34	$80.36
Operators (Building, Class 03 - See Notes)	5/1/2025		$41.88	$30.03	$71.91
Operators (Building, Class 03 - See Notes)	5/1/2026		$43.04	$30.87	$73.91
Operators (Building, Class 04 - See Notes)	5/1/2025		$40.74	$29.70	$70.44
Operators (Building, Class 04 - See Notes)	5/1/2026		$41.90	$30.54	$72.44
Operators (Building, Class 05 - See Notes)	5/1/2025		$40.30	$29.56	$69.86
Operators (Building, Class 05 - See Notes)	5/1/2026		$41.45	$30.41	$71.86
Operators (Building, Class 06 - See Notes)	5/1/2025		$39.42	$29.30	$68.72
Operators (Building, Class 06 - See Notes)	5/1/2026		$40.58	$30.14	$70.72
Operators (Building, Class 07A- See Notes)	5/1/2025		$54.56	$35.21	$89.77
Operators (Building, Class 07A- See Notes)	5/1/2026		$56.03	$36.14	$92.17
Operators (Building, Class 07B- See Notes)	5/1/2025		$54.22	$35.10	$89.32
Operators (Building, Class 07B- See Notes)	5/1/2026		$55.69	$36.03	$91.72
Painters Class 1 (see notes)	5/1/2024		$30.36	$24.15	$54.51
Painters Class 1 (see notes)	5/1/2025		$31.32	$24.44	$55.76
Painters - Line Stripping	12/1/2024		$44.12	$27.91	$72.03
Painters - Line Stripping	12/1/2025		$45.12	$29.41	$74.53
Painters Class 2 (see notes)	5/1/2025		$35.58	$25.08	$60.66
Painters Class 3 (see notes)	5/1/2025		$42.67	$25.09	$67.76
Pile Driver Divers (Building, Heavy, Highway)	1/1/2025		$62.82	$22.72	$85.54
Pile Driver Divers (Building, Heavy, Highway)	1/1/2026		$64.70	$23.47	$88.17
Piledrivers	1/1/2025		$41.88	$22.72	$64.60
Piledrivers	1/1/2026		$43.13	$23.47	$66.60
Plasterers	6/1/2024		$38.46	$14.45	$52.91
Plumbers and Steamfitters	12/1/2024		$51.49	$24.67	$76.16
Plumbers and Steamfitters	12/1/2025		$51.69	$27.67	$79.36
Roofers (Composition)	5/1/2024		$44.13	$34.77	$78.90
Roofers (Composition)	5/1/2025		$46.03	$34.77	$80.80
Roofers (Shingle)	5/1/2024		$34.35	$22.20	$56.55
Roofers (Slate & Tile)	5/1/2024		$37.35	$22.20	$59.55
Sheet Metal Workers	5/1/2024		$36.13	$31.23	$67.36
Sheet Metal Workers	5/1/2025		$37.30	$32.31	$69.61
Sign Makers and Hangars	7/15/2024		$32.32	$25.82	$58.14
Sign Makers and Hangars	7/15/2025		$33.48	$26.41	$59.89

BUREAU OF LABOR LAW COMPLIANCE
PREVAILING WAGES PROJECT RATES

Project: 26-03451 - Building	Effective Date	Expiration Date	Hourly Rate	Fringe Benefits	Total
Sprinklerfitters	4/1/2024		$46.45	$28.62	$75.07
Sprinklerfitters	4/1/2025		$49.75	$29.21	$78.96
Sprinklerfitters	4/1/2026		$52.82	$30.56	$83.38
Terrazzo Finisher	5/1/2024		$35.66	$20.76	$56.42
Terrazzo Finisher	5/1/2025		$36.32	$21.68	$58.00
Terrazzo Grinder	5/1/2024		$36.42	$20.76	$57.18
Terrazzo Grinder	5/1/2025		$37.10	$21.68	$58.78
Terrazzo Mechanics	5/1/2024		$36.44	$22.51	$58.95
Terrazzo Mechanics	5/1/2025		$37.17	$23.43	$60.60
Tile & Marble Finisher	5/1/2025		$34.55	$18.09	$52.64
Tile & Marble Finisher	5/1/2026		$36.50	$18.09	$54.59
Tile Setter	5/1/2025		$36.57	$21.69	$58.26
Tile Setter	5/1/2026		$38.52	$21.69	$60.21
Truckdriver class 1(see notes)	5/1/2025		$41.87	$0.00	$41.87
Truckdriver class 2 (see notes)	5/1/2025		$41.94	$0.00	$41.94
Truckdriver class 3 (see notes)	5/1/2025		$42.43	$0.00	$42.43
Window Film / Tint Installer	6/1/2019		$24.52	$12.08	$36.60
Window Film / Tint Installer	6/1/2024		$26.37	$14.83	$41.20
Window Film / Tint Installer	6/1/2025		$27.42	$15.13	$42.55

BUREAU OF LABOR LAW COMPLIANCE
PREVAILING WAGES PROJECT RATES

Project: 26-03451 - Heavy/Highway	Effective Date	Expiration Date	Hourly Rate	Fringe Benefits	Total
Carpenter	5/1/2025		$36.87	$20.49	$57.36
Carpenter	5/1/2026		$37.63	$21.18	$58.81
Carpenter Welder	5/1/2025		$37.62	$20.49	$58.11
Carpenter Welder	5/1/2026		$38.38	$21.18	$59.56
Carpenters - Piledriver/Welder	1/1/2025		$37.62	$20.49	$58.11
Carpenters - Piledriver/Welder	1/1/2026		$38.38	$21.18	$59.56
Cement Finishers	6/1/2016		$32.43	$11.35	$43.78
Electric Lineman	1/1/2025		$66.33	$30.40	$96.73
Electric Lineman	9/1/2025		$68.06	$32.29	$100.35
Iron Workers (Bridge, Structural Steel, Ornamental, Precast, Reinforcing)	7/1/2024		$37.26	$32.63	$69.89
Laborers (Class 01 - See notes)	5/1/2025		$26.61	$19.99	$46.60
Laborers (Class 01 - See notes)	5/1/2026		$27.61	$20.44	$48.05
Laborers (Class 02 - See notes)	5/1/2025		$33.23	$19.99	$53.22
Laborers (Class 02 - See notes)	5/1/2026		$34.23	$20.44	$54.67
Laborers (Class 03 - See notes)	5/1/2025		$30.22	$19.99	$50.21
Laborers (Class 03 - See notes)	5/1/2026		$31.22	$20.44	$51.66
Laborers (Class 04 - See notes)	5/1/2025		$30.57	$19.99	$50.56
Laborers (Class 04 - See notes)	5/1/2026		$31.57	$20.44	$52.01
Laborers (Class 05 - See notes)	5/1/2025		$31.24	$19.99	$51.23
Laborers (Class 05 - See notes)	5/1/2026		$32.24	$20.44	$52.68
Laborers (Class 06 - See notes)	5/1/2025		$30.66	$19.99	$50.65
Laborers (Class 06 - See notes)	5/1/2026		$31.66	$20.44	$52.10
Laborers (Class 07 - See notes)	5/1/2025		$30.95	$19.99	$50.94
Laborers (Class 07 - See notes)	5/1/2026		$31.95	$20.44	$52.39
Laborers (Class 08 - See notes)	5/1/2025		$31.43	$19.99	$51.42
Laborers (Class 08 - See notes)	5/1/2026		$32.43	$20.44	$52.87
Millwright	6/1/2025		$45.46	$23.33	$68.79
Millwright	6/1/2026		$47.52	$23.33	$70.85
Operators (Heavy, Class 01 - See Notes)	5/1/2025		$43.46	$30.50	$73.96
Operators (Heavy, Class 01 - See Notes)	5/1/2026		$44.61	$31.35	$75.96
Operators (Heavy, Class 01A - See Notes)	5/1/2025		$45.71	$31.16	$76.87
Operators (Heavy, Class 01A - See Notes)	5/1/2026		$46.86	$32.01	$78.87
Operators (Heavy, Class 02 - See Notes)	5/1/2025		$43.18	$30.41	$73.59
Operators (Heavy, Class 02 - See Notes)	5/1/2026		$44.34	$31.25	$75.59
Operators (Heavy, Class 02A - See Notes)	5/1/2025		$45.43	$31.08	$76.51
Operators (Heavy, Class 02A - See Notes)	5/1/2026		$46.59	$31.92	$78.51
Operators (Heavy, Class 03 - See Notes)	5/1/2025		$40.26	$29.55	$69.81
Operators (Heavy, Class 03 - See Notes)	5/1/2026		$41.43	$30.38	$71.81
Operators (Heavy, Class 04 - See Notes)	5/1/2025		$39.12	$29.22	$68.34
Operators (Heavy, Class 04 - See Notes)	5/1/2026		$40.28	$30.06	$70.34
Operators (Heavy, Class 05 - See Notes)	5/1/2025		$38.67	$29.09	$67.76
Operators (Heavy, Class 05 - See Notes)	5/1/2026		$39.83	$29.93	$69.76
Operators (Heavy, Class 06 - See Notes)	5/1/2025		$37.80	$28.82	$66.62
Operators (Heavy, Class 06 - See Notes)	5/1/2026		$38.96	$29.66	$68.62

BUREAU OF LABOR LAW COMPLIANCE
PREVAILING WAGES PROJECT RATES

Project: 26-03451 - Heavy/Highway	Effective Date	Expiration Date	Hourly Rate	Fringe Benefits	Total
Operators (Heavy, Class 07A - See Notes)	5/1/2025		$52.85	$34.71	$87.56
Operators (Heavy, Class 07A - See Notes)	5/1/2026		$54.32	$35.64	$89.96
Operators (Heavy, Class 07B - See Notes)	5/1/2025		$52.51	$34.60	$87.11
Operators (Heavy, Class 07B - See Notes)	5/1/2026		$53.97	$35.54	$89.51
Operators (Highway, Class 01 - See Notes)	5/1/2025		$42.56	$30.24	$72.80
Operators (Highway, Class 01 - See Notes)	5/1/2026		$43.72	$31.08	$74.80
Operators (Highway, Class 01a - See Notes)	5/1/2025		$44.81	$30.92	$75.73
Operators (Highway, Class 01a - See Notes)	5/1/2026		$45.97	$31.76	$77.73
Operators (Highway, Class 02 - See Notes)	5/1/2025		$41.39	$29.89	$71.28
Operators (Highway, Class 02 - See Notes)	5/1/2026		$42.55	$30.73	$73.28
Operators (Highway, Class 03 - See Notes)	5/1/2025		$40.70	$29.68	$70.38
Operators (Highway, Class 03 - See Notes)	5/1/2026		$41.87	$30.51	$72.38
Operators (Highway, Class 04 - See Notes)	5/1/2025		$40.26	$29.54	$69.80
Operators (Highway, Class 04 - See Notes)	5/1/2026		$41.41	$30.39	$71.80
Operators (Highway, Class 05 - See Notes)	5/1/2025		$39.73	$29.41	$69.14
Operators (Highway, Class 05 - See Notes)	5/1/2026		$40.89	$30.25	$71.14
Operators (Highway, Class 06 - See Notes)	5/1/2025		$42.80	$30.30	$73.10
Operators (Highway, Class 06 - See Notes)	5/1/2026		$43.95	$31.15	$75.10
Operators (Highway, Class 06/A - See Notes)	5/1/2025		$45.05	$30.96	$76.01
Operators (Highway, Class 06/A - See Notes)	5/1/2026		$46.21	$31.80	$78.01
Operators (Highway, Class 07/A - See Notes)	5/1/2025		$51.79	$34.38	$86.17
Operators (Highway, Class 07/A - See Notes)	5/1/2026		$53.25	$35.32	$88.57
Operators (Highway, Class 07/B - See Notes)	5/1/2025		$50.37	$33.97	$84.34
Operators (Highway, Class 07/B - See Notes)	5/1/2026		$51.84	$34.90	$86.74
Painters - Line Stripping	12/1/2024		$44.12	$27.91	$72.03
Painters - Line Stripping	12/1/2025		$45.12	$29.41	$74.53
Painters Class 2 (see notes)	5/1/2024		$34.16	$24.75	$58.91
Painters Class 3 (see notes)	5/1/2024		$41.01	$24.75	$65.76
Pile Driver Divers (Building, Heavy, Highway)	1/1/2022		$56.40	$20.50	$76.90
Piledrivers	5/1/2025		$36.87	$20.49	$57.36
Piledrivers	5/1/2026		$37.63	$21.18	$58.81
Steamfitters (Heavy and Highway - Gas Distribution)	5/1/2025		$54.39	$44.73	$99.12
Truckdriver class 1(see notes)	5/1/2025		$41.87	$0.00	$41.87
Truckdriver class 2 (see notes)	5/1/2025		$41.94	$0.00	$41.94
Truckdriver class 3 (see notes)	5/1/2025		$42.43	$0.00	$42.43